

INDIANA DEPARTMENT OF TRANSPORTATION

Production Management Division

Proudly Presents:



Those strongly encouraged to attend:

INDOT Production Staff (Districts and Central Office)

- Road, Bridge and Traffic Designers
- Project Managers

No more than one representative from each consultant pre-qualified in the following work type descriptions:

- 8.1 Non-complex Roadway Design
- 8.2 Complex Roadway Design
- 9.1 Level 1 Bridge Design
- 9.2 Level 2 Bridge Design
- 10.1 Traffic Signal Design
- 10.2 Traffic Signal System Design
- 10.3 Complex Roadway Sign Design
- 10.4 Lighting Design
- 10.5 Intelligent Transportation System Design

Highlighted Topics:

- ADA
- 3 Sided and 4 Sided Precast Structures
- Consultant Evaluation and Expectations
- Design Exception Justification
- Utility Coordination
- MOT Best Practices
- Roadside Safety and Guardrail Design
- Road Design and Bridge Design Breakouts

Monday, April 28, 2008
Indiana Government Center South
Conference Center Room A-C
8:00 AM to 4:00 PM
(Pre-Registration ends April 18th)

MAJOR MOVES

BUILDING/TRANS. DIVISION/INDOT

INDIANA DEPARTMENT OF TRANSPORTATION

To register (Email preferred), please contact:
Gary Mroczka, Director
100 N. Senate Avenue, Room M647
Indianapolis, Indiana 46204-2216

Work: 317-232-5226
Cell: 317-694-2193
E-mail: gmroczka@indot.in.gov





Road Design Breakout Session

Roadway Services:

- What parts of Roadway Services interacts with Consultants?
- Standards Section
- Review Section
- Traffic Section



Road Design Breakout Session

Published Road Design breakout Session

- New or recently published Design Standards / Procedures / Policies
- Partial 3R v 3R v 4R
- New Superelevation / Shoulder break
- Calculating Inlet Spacings / Layout of Storm Sewers



Road Design Breakout Session


Published Road Design breakout Session

We will discuss most of these items, but the itinerary has been changed to include items from each of the following;

Standards Unit (1st Group)


Review Team (2nd Group)

Traffic Team (3rd Group)




Road Design Breakout Session (Standards Section) (1st Group)

- Cable Barrier
- Bicycle Facilities (Shared-Use Paths)
- Best Practices for Inlets and Storm Sewers (in lieu of Inlet Spacings & Storm Sewers)
- New Superelevation / Shoulder Break



Road Design Breakout Session (Review Section) (2nd Group)

- ERMS Information
- Recent Design Memos
- Annual Construction Evaluation Report



Road Design Breakout Session (Traffic Section) (3rd Group)


- Traffic Squad (IPOC Projects)
- Signal Design Memo
- New Standards for Sign Trusses



Road Design Breakout Session (Standards Section)


- Cable Barrier

(Yadu Shah)



Cable Barrier System (CBS)


High-Tension CBS NCHRP
Report 350, Test Level 4
(TL-4)

- 
- There are no changes in design of rigid (concrete) and semi flexible (W-Beam and Thrie-Beam) barriers.
 - INDOT will use a new barrier type, a flexible barrier, high-tension cable barrier system (CBS) for median installation.
 - This CBS should be considered in the median of a high-speed, high traffic volume roadway where fatal median-crossover crashes have been reported or are anticipated.
 - The CBS consists of 4 pre-stretched, individually anchored wire ropes in tension between safety terminal and held in position by intermediate line posts.




Why Cable Median Barrier?

- To avoid median-crossover crashes
- To reduce disabling injuries
- To save lives
- To decrease fatal crash costs
- Cable median barriers are safe, effective, cost efficient and have proven results

- 
- INDOT will use high-tension pre-stretched 4 wire rope TL-4 CBS.
 - CBS intermediate line post will have a socket tube cast-in-place in concrete for easy removal and replacement of line posts after vehicle impact.
 - The contractor will select CBS from INDOT approved product list of CBS.
 - All CBS in approved product list are proprietary items.
 - INDOT will install 150 miles of CBS at a cost of approx. \$22 million in 2008 and 2009.



Proposed Locations
Cable Median Barrier
Interstate System



Map Prepared by
Office of Highway Safety and Mobility Coordinator
02 June 2007

Legend

- Proposed Location of Cable Median Barrier
- Interstate Highway System
- Indiana Toll Road

**Case for Median Barrier Installation on Select Segments of Rural Interstate System
(Statewide)**

Interstate Route No.	Begin RP	End RP	Segment Length (mi)	District/Sub-district	Des No.
I-64	117.00	120.00	3.00	S/Falls City Sub	0710151
I-64	121.10	121.40	0.30	S/Falls City Sub	0710151
I-65	93.40	95.60	2.20	S/Falls City Sub	0710152
I-65	98.90	20.00	11.20	S/Falls City Sub	0710150
I-65	44.00	54.94	10.94	S/Mad. and Colum. Sub	0710150
I-65	79.60	84.00	4.40	S/Mad. and Colum. Sub	0710150
I-65	84.45	98.47	14.02	S/Mad. and Colum. Sub	0710150
I-65	142.25	146.30	4.05	Crawford/Frankfort	0710149
I-65	157.30	183.00	25.70	Crawford/Frankfort&Fowler	0710149
I-65	192.70	198.00	5.30	Crawford/Frankfort&Fowler	0710149
I-65	218.00	220.80	2.80	LaPorte/Rensselaer	0710146
I-65	228.00	229.90	1.90	LaPorte/Rensselaer	0710146
I-80/I-90	21.10	24.00	2.90	LaPorte/LaPorte	0710145
I-80/I-90	71.00	77.30	6.30	LaPorte/Plymouth	0710145
I-74	65.37	73.20	7.83	Crawford/Cloverdale	0710148
I-70	04.39	11.40	7.01	Crawford/Terre Haute	0710147
I-70	58.90	60.70	1.80	Crawford/Cloverdale	0710147
I-70	62.50	68.41	5.91	Crawford/Cloverdale	0710147
I-70	68.61	69.06	0.45	Crawford/Cloverdale	0710147
I-70	69.06	72.50	3.44	Greenfield/Indy	0710143
I-70	91.20	92.80	1.60	Greenfield/GF	0710143
I-70	93.80	104.50	10.70	Greenfield/GF	0710143
I-70	145.80	151.80	6.00	Greenfield/Centerville	0710143
I-75	125.90	130.10	4.20	Polk/Laurens/Albion	0710144

CBS with High-Tension Pre-Stretched Cables

Why High-Tension CBS


- Tensioning cables after installation improves the performance of the system by reducing deflection and increasing the potential to capture the impacting vehicle.
- High-tension system also results in less damage to the barrier after a vehicle impact.
- Has low maintenance cost

Why Pre-Stretched Cables


- Reduced dynamic deflection
- From the experience, contractors find it easier to tension

Roadway Design: Side Slope and Placement


- Avoid placing CBS in the median ditch due to conflicts with drainage inlets and dikes. These locations may be wet and offer poor support for post and anchor foundation.
- Maximum 8 feet deflection allowed at maximum 16 feet post spacing side slopes 6:1 or flatter.
- 16 feet from edge of travel lane with 4 feet paved shoulder width
- 8 feet from centerline of V ditch or 10 feet from centerline of flat bottom ditch line (4 feet wide ditch)
- The above placement of CBS requires a minimum median width of 48 feet for V ditch and 52 feet for flat bottom ditch.
- Lateral clearance to a rigid obstacle such as a bridge pier, sign support, utility pole, tree, etc, should be minimum 10 feet.
- A minimum lateral clearance of 10 feet from other parallel barriers (concrete barrier or W-Beam Guardrail)
- Geotechnical information will require to determine sizes of safety terminal foundations and line post foundations prior to installation of CBS.





ELEVATION
LOCATION OF CBS IN MEDIAN



ELEVATION
TYPICAL CBS LAYOUT



DETAIL A



DETAIL B
MINIMUM SIZE AND REINFORCEMENT FOR
LINE POST FOUNDATION FOR CBS TL-4 SYSTEM


NOTES:

1. CBS: Cable Barrier System.
- ② Regrading of slope shall not extend beyond the centerline of the median and shall not impact the existing ditch flow line.
3. Cable barrier placement detail shown on this drawing is applicable to median with a maximum paved shoulder width of 4 ft. and the following median widths:
 - a. A minimum median width of 48 ft. for a V ditch
 - b. A minimum median width of 52 ft. for a 4 ft. wide flat bottom ditch.
4. CBS horizontal alignment transitions shall be made on a 50:1 or flatter taper.

INDIANA DEPARTMENT OF TRANSPORTATION
LOCATION OF CBS IN MEDIAN


BRIFEN★USA INC.

WIRE ROPE SAFETY FENCE



NCHRP 350 APPROVED

Proven Design. Years of Real World Performance



Because You Only Want The Very Best

Road Design Breakout Session (Standards Section)

- Bicycle Facilities
(Shared-Use Paths)

(Brian Zafar)

Bicycle Facilities

Shared Use Paths

Introduction

- The purpose of the Indiana Bicycle Facilities Section in the INDOT Design Manual is to provide engineers, planners and designers with a primary source of guidance to implement the Indiana Trails, Greenways and Bikeways plan. Safe, convenient and well-designed facilities are essential to encourage bicycle use. This guide is designed to provide information on the development of facilities to enhance and encourage safe bicycle travel. The majority of bicycling will take place on ordinary roads with no dedicated space for bicyclists. Bicyclists can expect to ride on almost all roadways, as well as separated shared use paths and even sidewalks, where permitted, when special conditions warrant.

- This guide provides information to help accommodate bicycle traffic in most riding environments. It is not intended to set forth strict standards, but rather, to present sound guidelines that will be valuable in attaining good design, sensitive to the needs of both bicyclists and other users. However, in some sections of this guide, design criteria include suggested minimum guidelines. These are recommended only where further deviation from desirable values could result in unacceptable safety compromises.
- This Section regarding the design of bicycle facilities should be used in conjunction with other Sections in the IDM, the Indiana Manual on Uniform Traffic Control Devices (IN MUTCD) and the American Association of State Highway and Transportation Officials (AASHTO) Guide for the Development of Bicycle Facilities (1999).

Table of Contents

- **51-7.0 BICYCLE FACILITIES**
- 51-7.10 BIKEWAY DEFINITIONS
- 51-7.20 GUIDELINES
 - 51-7.21 Bicycle Paths
 - 51-7.22 Bicycle Lanes
 - 51-7.23 Shared Roadway
- 51-7.30 SELECTION
- 51-7.40 GENERAL DESIGN FACTORS
 - 51-7.41 Bicycle Operating Space and Characteristics
 - 51-7.42 Types of Bicyclists
 - 51-7.43 Selecting the Bikeway Path
 - 51-7.44 Bikeway Types
 - 51-7.45 Accessible Design

Table of Contents (continued)

51-7.50 SHARED-USE PATHS

- 51-7.51 Shared-Use Paths
- 51-7.51(01) Geometric Design of Shared-Use Paths
 - 51-7.51(01.1) Separation Between Path and Roadway
 - 51-7.51(01.2) Snow Storage in Separation Areas
 - 51-7.51(01.3) Design Speed
 - 51-7.51(01.4) Shared-Use Path Widths and Lateral Clearances
 - 51-7.51(01.5) Vertical Clearances
 - 51-7.51(01.6) Horizontal Curvature and Superelevation
 - 51-7.51(01.7) Grade
 - 51-7.51(01.8) Sight Distance
 - 51-7.51(01.9) Sight Distance at Horizontal Curves
 - 51-7.51(01.10) Intersection Sight Distance (ISD)

Table of Contents (continued)

- 51-7.51(02) Path/Roadway Intersection Treatment Selection/Design
 - 51-7.51(02.1) Mid-block Crossings
 - 51-7.51(02.2) Adjacent Path Crossings
 - 51-7.51(02.3) Complex Intersection Crossings
 - 51-7.51(02.4) Other Intersection Design Issues
 - 51-7.51(02.5) Paths and At-Grade Railroad Crossings
- 51-7.51(03) Pavement Structure
- 51-7.51(04) Drainage
 - 51-7.51(04.1) Transportation Enhancement trail Projects
- 51-7.51(05) Signing and Marking
- 51-7.51(06) Lighting
- 51-7.51(07) Structures
- 51-7.51(08) Restriction of Motor Vehicle traffic
- 51-7.51(09) Bicycle Parking Facilities
- 51-7.52 Trails
- 51-7.53 Greenways

- **51-7.30 SELECTION**

- A local governmental agency will determine the bikeway type and location for the bicycle facility during the planning stages. If it is determined that a bicycle facility is feasible and can be properly funded, the designer should coordinate with the agency in the design of the bikeway facility.

- **51-7.50 SHARED - USE PATHS**

- **Introduction**

- **51-7.51 Shared-Use Paths**

- Shared-use path is a term adopted by the 1999 AASHTO Guide for the Development of Bicycle Facilities in recognition that paths are seldom, if ever, used only by bicycles. A shared-use path is typically located on exclusive right-of-way, with no fixed objects in the pathway and minimal cross flow by motor vehicles. Portions of a shared-use path may be within the road right-of-way but physically separated from the roadway by a barrier or landscaping. Users typically include bicyclists, in-line skaters, wheelchair users (both non-motorized and motorized) and pedestrians, including walkers, runners, people with baby strollers or dogs with people. Shared-use paths are usually designed for two-way travel except under special conditions. The guidance in this manual is for two-way facilities unless otherwise stated.

- **51-7.51(01) GEOMETRIC DESIGN OF SHARED-USE PATHS**
- The following sections provide guidelines for geometric design of shared-use paths. These guidelines are intended to be applied using a flexible design approach. Where recommended minimum design standards cannot be met due to right-of-way limits or other constraints, a detailed safety analysis should be conducted to determine the best compromise design solution and apply for a design exception from the INDOT Roadway Services Manager.
- **51-7.51(01.1) Separation Between Path and Roadway**
- When a two-way shared-use path is located adjacent to a roadway, a wide separation between the shared-use path and adjacent highway is desirable, demonstrating to both the bicyclist and the motorist that the path functions as an independent facility. The factors in determining how far away a shared-use path should be separated from the roadway include the posted speed of the road, the type of signs between the path and roadway, the amount of space available, and whether the roadway has a rural (shoulder and ditch) cross section or urban (curb and gutter) cross section.
- The separation distance between a path and a roadway depends primarily on the posted speed limit of the road. Recommended separations for rural (shoulder and ditch) and urban (curb and gutter) road cross sections are illustrated in **Figures 51-7C** and **Figure 51-7E** and detailed in **Figure 51-7D** and **Figure 51-7F**.

- **51-7.51(01.3) Design Speed**

- For the general design of shared-use paths, a bicycle design speed of **20 mph** is desirable. For descending grades **500 ft** or longer and **4%** or steeper grades, a bicycle design speed of **30 mph** is desirable. On unpaved paths, where bicyclists tend to ride more slowly, a bicycle design speed of **15 mph** may be used. However, since skidding is more common on unpaved surfaces, horizontal curvature design should take into account a lower coefficient of friction. The selected design speed should be maintained throughout the length of the shared-use path. Alternating design speeds is not recommended. If site conditions will not allow the appropriate path geometrics for the selected design speed, then, a lower design speed should be selected for the path except where a portion of the path is in a rural area and another path is in an urban area.

NOTE: All other slides presented in the Bicycle Chapter session have been deleted from this powerpoint to conserve space. The Chapter will be put online as soon as Commissioner Browning reviews it.

Road Design Breakout Session (Standards Section)

- Best Practices for Inlets and Storm Sewers
(in lieu of Inlet Spacings & Storm Sewers)
- New Superelevation / Shoulder Break

(Richard VanCleave)

Best Practices for Inlets and Storm Sewers

- I. Introduction – This is a brief review of some items, many of which are found in the Design Manual, often overlooked or misinterpreted in the plan development process
- II. Inlet Related Items
 - A. Inlet Locations (also Catch Basins)
 - 1. Always place Upstream of:
 - a) Driveways
 - b) Streets
 - c) Sidewalk curb ramps
 - d) Pedestrian walkways (crosswalks)
 - e) Reversals in pavement cross slopes

Best Practices for Inlets and Storm Sewers

- f) Bridge decks

- g) In gore areas – Interchange ramps, etc.

2. Roadside

- a) Low spots adjacent to lawn

- b) In ditches intercepting sheet flow

3. Sags in gutter grade

- a) Short run – double frame inlet, grates properly aligned to accept flow

- b) Medium run – inlet plus one flanking inlet

- c) Long run – inlet plus two flanking inlets

Best Practices for Inlets and Storm Sewers

B. Driveway Treatments to Contain Gutter Flow

1. Provide slight hump in driveway grade near gutter line for down grade driveways
2. Provide face of curb line lip 1 to 1 ¼" high past drive entrance

C. Pavement Grades

1. Minimum longitudinal – 0.3%
2. Flat < 0.3% - roll gutter grade with inlet in sag
3. Slotted drains may be utilized

D. Utilities – coordinate location/elevation of pipes

Best Practices for Inlets and Storm Sewers

E. Grates

1. Should be bicycle safe where bicycles permitted
2. Grate width (transverse) should not exceed gutter width
3. Should be compatible with inlet/catch basin boxes
4. Correct orientation of vane grates (basically a construction problem)

F. Slotted Drain Usage

1. High side shoulder on superelevated pavements – longitudinally
2. Angled out from H-5 inlets in median shoulders next to concrete barriers

Best Practices for Inlets and Storm Sewers

- c. Two smaller trunk lines, one on each side of roadway to avoid multitude of cross pipes under pavement or to better meet outfall elevation in flat areas
 - d. If no other option, place under center of right lane out of wheel tracks to avoid manhole cover clatter when vehicles pass over
 - e. Thoroughly review utility locations to avoid conflicts
- H. Properly size manhole to accept all entering and exiting pipes while maintaining structural integrity of the manhole

Best Practices for Inlets and Storm Sewers

I. Assure adequate fall available to drain sewer – if in ditch, may have to provide extra wide outlet ditch to provide some detention capability

III. Shoulder Slope Break Point

A. Typical shoulder slope break point is at the right edge of the outside through travel lane

1. Exception – On PCCP with 14 foot wide right outside lane and HMA shoulder, slope break occurs at outside edge of 14 foot wide lane

Best Practices for Inlets and Storm Sewers

2. PCCP with concrete shoulders, slope break point is at right edge of outside travel lane
3. HMA pavements – Shoulder slope break point at right edge of outside travel lane


B. Underdrains

1. Subbase drainage layers extend out to and over underdrains
2. Shoulder surface lays extend over underdrains
3. Current 45-degree slope angles from outside edge of outside travel lane are used to set location of underdrains

Best Practices for Inlets and Storm Sewers

C. Chapter 52 – Currently being reviewed and revised with some typical section revisions which will further clarify the dimensions, etc.

New Superelevation / Shoulder Break




* All Pavement, Including All Shoulders

- ① 165 lb/yd² HMA Surface 9.5 mm
- ② 275 lb/yd² HMA Intermediate 19.0 mm
- ③ 440 lb/yd² Minimum HMA Base 25.0 mm
- ** ④ 440 lb/yd² QC/QA-HMA Intermediate OG25.0 mm
- ⑤ 440 lb/yd² HMA Base 25.0 mm
- ⑥ Subgrade Treatment
- ⑦ Variable-Depth Compacted Aggregate, No. 53
- ⑧ Pipe, Type 4, Circular, 6 in.


* Open graded mixtures OG19.0 mm or OG25.0 mm should be QC/QA-HMA, 5, 76. For all other mixtures, see Section 52-9.02 to determine the appropriate HMA mixture designation.

** If underdrain warrants are not met, Intermediate OG25.0 mm mix should be replaced with HMA Base 25.0 mm, minimum 495 lb/yd².



**FULL DEPTH HMA PAVEMENT,
≥ 30 MILLION ESALs
Figure 52-13A**

New Superelevation / Shoulder Break



* Mainline

- ① 165 lb/yd² HMA Surface 9.5 mm
- ② 275 lb/yd² HMA Intermediate 19.0 mm
- ③ 440 lb/yd² HMA Base 25.0 mm
- ** ④ 300 lb/yd² QC/QA-HMA Intermediate OG25.0 mm
- ⑤ 440 lb/yd² HMA Base 25.0 mm
- ⑥ Subgrade Treatment
- ⑩ Pipe, Type 4, Circular, 6 in.

* Shoulders


- ⑦ 165 lb/yd² HMA Surface 9.5 mm
- ⑧ 495 lb/yd² HMA Base 25.0 mm
- ⑨ Compacted Aggregate, No. 53, Base
(Depth equals mainline HMA thickness minus 6 in.)
- ⑪ Variable-Depth Compacted Aggregate, No. 53

* Open graded mixtures OG19.0 mm or OG25.0 mm should be QC/QA-HMA, 5, 76. For all other mixtures, see Section 52-9.02 to determine the appropriate HMA mixture designation.

** Where underdrains are not required, QC/QA-HMA Intermediate OG25.0 mm mix should be replaced with HMA Base 25.0 mm, 330 lb/yd².

FULL DEPTH HMA PAVEMENT,
10 MILLION ≤ ESALs < 30 MILLION
Figure 52-13B

New Superelevation / Shoulder Break



* Mainline Pavement (Section With Shoulders)

- ① 165 lb/yd² HMA Surface 9.5 mm
- ② 275 lb/yd² HMA Intermediate 19.0 mm
- ③ 275 lb/yd² HMA Base 19.0 mm
- ** ④ 275 lb/yd² Minimum QC/QA-HMA Intermediate OG 19.0 mm
- ⑤ 330 lb/yd² QC/QA-HMA Base 19.0 mm
- ⑥ Subgrade Treatment
- ⑩ Pipe, Type 4, Circular, 6.0 in.

* Shoulders



- ⑦ 165 lb/yd² HMA Surface 9.5 mm
- ⑧ 495 lb/yd² HMA Base 25.0 mm
- ⑨ Compacted Aggregate Base

* Open graded mixtures OG 19.0 mm or OG 25.0 mm should be QC/QA-HMA, 5, 76. For all other mixtures, see Section 52-9.02 to determine the appropriate HMA mixture designation.

** If underdrain warrants are not met, Intermediate OG 19.0 mm mix should be replaced with HMA Base 19.0 mm minimum 495 lb/yd².

FULL DEPTH HMA PAVEMENT,
1 MILLION ≤ ESALs <10 MILLION
Figure 52-13C

New Superelevation / Shoulder Break



Mainline and Shoulders


- ① PCCP
- * ② Subbase for PCCP (3 in. Coarse Aggregate No.8 On 6 in. Coarse Aggregate No.53, Base)
- ②A 6 in. Compacted Aggregate, No. 53, Base
- ③ Variable-Depth Compacted Aggregate, No. 53
- ④ Pipe, Type 4, Circular, 6 in.
- ⑤ Subgrade Treatment
- ⑥ Longitudinal Joint or Longitudinal Construction Joint. See Figure 52-13R for Pavement Joint Options.
- ⑦ Concrete Median Barrier

* Where underdrains are not required, Dense Graded Subbase should be used.

PCCP SECTION WITH PCC SHOULDER, ≥ 30 MILLION ESALs

Figure 52-13F

New Superelevation / Shoulder Break



Mainline

- ① PCCP
- * ② Subbase for PCCP (3 in. Coarse Aggregate No.8 On 6 in. Coarse Aggregate No.53, Base)

Shoulders

- ** ③ 165 lb/yd² HMA Surface 9.5 mm
330 lb/yd² HMA Intermediate 19.0 mm
- ** ④ HMA Base 25.0 mm
- ⑤ Compacted Aggregate, No. 53, Base
- ⑥ Variable-Depth Compacted Aggregate, No. 53
- ⑦ Subgrade Treatment
- ⑧ Longitudinal Joint or Longitudinal Construction Joint
- ⑨ Pipe, Type 4, Circular, 6 in.

* Where underdrains are not required, Dense Graded Subbase should be used.

** See Section 52-9.02 to determine the appropriate HMA mixture designation.

PCCP SECTION WITH HMA SHOULDER, < 30 MILLION ESALs

Figure 52-13G

Road Design Breakout Session (Review Section)

- ERMS Information
- Recent Design Memos
- Annual Construction Evaluation Report


Road Design Breakout Session (Review Section)


- ERMS Information (Shariq Husain)
- Recent Design Memos (John Wright)
- Annual Construction Evaluation Report (John Wright)

ERMS Update

- CO Coordinator 7 processes about 300-400 projects per month.
- Goal is to transition projects within 2 days or less
- Improvements have been made to the system
- Additional staff has been added (3 people now have role as coordinator 7)

ERMS Project Submittal Process





ERMS Improvements

- **Changes in the workflow (see the attached diagram)**
 - Add a route for non-IPOC projects designed by Central Office (CO) to go from Submit for Review state to Consultant Coord (DCSC) state.
 - Add a route for Consultant Coord (Dist. Coord) to transition docs from Consultant Coord (DCSC) state to CS Review (Contracts Review) state.
 - Add a route for CO Coord to transition docs from CO Review state to CS Review (Contracts Review) state
 - Add a route for CO Coord to transition docs from CO Review state to Consultant Coord (DCSC) state
 - Add a route for Consultant Coord (Dist. Coord) to transition docs from Review Complete – Non IPOC to District Review state

ERMS Improvements

- **Changes in security**

- Grant view access to everybody who has been involved in the project, up to CS Review (Contracts Review) state.
- Grant owner access (view, change, delete) to coordinators up to CS Review (Contracts Review) state.

- **Messaging**

- Auto email to the designer, coordinator and project manager whenever the set of design documents arrives at Consultant Submit, Consultant Coord (DCSC) and CO Coord states. Use the Transmittal Letter as the tracking sheet.

- **Reporting**

- A report on the time spent by each document at Consultant Coord (DCSC), District Review, CO Coord and CO Review states.
- A report on the documents sitting in a smart folder.

File Title Naming Rules

Title Naming Rules

Use the title to identify the contents of the document, here are examples;

Submittal, Des #, Office of Review, What it is

Hyd 0012345 for Bridge Services, **Memo**
Services

Insp 0012345 for Bridge Services, **Letter**
Services

Scour 0012345 for Bridge Services, **Calc**

GR 0012345 for Roadway Services, **Plans**

PFC 0012345 for Rdwy or Bridge Serv, **Plans**

STG 1 0012345 for Rdwy or Bridge Ser, **Letter**

What does it mean?

Hydraulic review going to Bridges

Inspection Report for Br. Rehabs for Br

Scour calc being sent to Bridge Services

Grade Review

Preliminary Field Check

Stage 1 Plans (new PDP process)

Design Memorandums

A reminder to all to review the Design Memorandums on the INDOT Website. A few of the most recent ones are listed below (please be aware of when the memo is effective):

DM 07-13, Structural Backfill and Flowable Backfill, 10/16/07

Summary: Confusion on a recent letting. A few contracts did not incorporate into the plans. It is currently in the process of being revised to clear up confusion.

DM 07-14, Plan Development Process, 12/21/07

Summary: Indicates that Chapter 14 has been revised to match the PDP Manual. The revised Chapter is effective immediately for projects that have not received a notice to proceed. For Projects in the process, whether or not to use the new version will be made by either the District or Central Office.

DM 08-02, Use of Indiana Design Manual, English-Units Version, 3/18/08

Summary: This is a clarification. English units version of the Design Manual must be used for the design of each project for which design work was begun in english units. The metrics units version for all parts must continue to be used for each project for which design work was begun in metric units.

Design Memorandums

DM 08-03, Federal Aviation Administration (FAA) Tall-Structure Permit, 3/18/08

Summary: The FAA no longer issues a Navigable Airspace Permit. The new formal name is Indiana Tall-Structure Permit (informal name is Tall Structure Permit). Permit is obtained from the Local Programs Division's Office of Aviation where proposed construction may impact the navigable airspace of a public-use airport.

DM 08-05, Temporary Seeding, 3/18/08

Summary: Temporary-seeding related pay items have been left out on a number of let contracts, especially in multi-phase contracts in urban areas. Erosion control is currently receiving additional scrutiny from both IDEM and the Department's environmental personnel. The designer should be alert to recognize each work area where soil will be disturbed by construction operations and is likely to remain in an uncovered state for an extended period of time.

NOTE: Multi-season contracts need temporary mulching, in many cases, an item is not included (memo may be forthcoming)

DM 08-06, Temporary Pavement Markings, 4/18/08

Summary: emphasizes the guidelines and applications for: Paint, Temporary Raised Pavement Markings, Temporary Pavement Marking Tape, Thermoplastic/ Epoxy Markings and Buzz Strips.

Design Memorandums

Doing Business with INDOT - Microsoft Internet Explorer provided by Division of System Technology

File Edit View Favorites Tools Help

Back Forward Stop Home Search Favorites Media

Address <http://www.in.gov/dot/div/contracts/standards/memos/memos.html> Go Links

Search Web Upgrade your Toolbar Now! Mail My Yahoo! HotJobs

[About Indiana](#)
[Agriculture & Environment](#)
[Business & Employment](#)
[Education & Training](#)
[Family & Health](#)
[Law & Justice](#)
[Public Safety](#)
[Taxes & Finance](#)
[Tourism & Transportation](#)

Find an Agency Find a Person HELP

INDOT Home

- About INDOT
- Motorist Information
- Publications
- Modes of Transportation
- Doing Business with INDOT
- Projects / Studies
- Public Involvement / Media
- Programs / Events
- Quick Links**
- Current Letting Summaries
- Contact Us
- Public Service Links
- News
- What's New
- Site Map
- Most Visited**
- Major Moves
- Permits
- FAQ's
- GIS
- Forms
- Careers

Design Memorandums and Memos

[Click here to print Design Memorandums Index](#)

[link to archived memos](#)

[Link to Construction Memorandums](#)

All Design Memos issued prior to July 8, 2005 except the following, have been deleted from this list.

Number	Memo Date	Effective Date	Affected Design Manual Section	Subject	PDF Files		
					Policy	Advisory	Attachments
08-06	04/18/08	09/04/08, letting	Indiana Design Manual Section 83-4.0	Temporary Pavement Markings		Advisory	801-T-165 PDF
08-05	03/18/08	Immediately	17-3.10 (04)	Temporary Seeding		Advisory	
			Indiana Design Manual PDP Chapter 14 Section 14-2.04				

Request a 2007/2008 Indiana State Map

Trusted sites

12:54 PM

Start In... 05... IB... IN... D... M... IN... D... Mi... C... A...

Annual Construction Evaluation Report

Overview:

In 2005 the INDOT Roadway Services Section had Janssen and Spaans Engineering (JSE) compile the Construction Evaluations of Plans and Contract Documents for projects all over the state. The Construction Evaluations were for projects completed **between 1999 and 2004**. After reviewing and compiling all the evaluations, JSE summarized the information into a Report. The Report summarizes trends, common errors and issues.

The first Report was completed in June 2005. Since then there have been updates to the report. The **2007 Report** was sent to the Districts for comments and suggestions. We are currently in the process of summarizing the information.

NOTE: This report will be enhanced by 5 other reports;

Stage 1 Constructability Review evaluation

Stage 2 Constructability Review evaluation

Stage 3 Constructability Review evaluation

Pre-bid evaluation

Mid-Construction evaluation

Post Construction evaluation

INDOT Construction Evaluation Report



State Form 48625 (4-84)

Indiana Department of Transportation

INSTRUCTIONS

INDOT's Construction representative shall complete this form at predetermined intervals during construction and at the conclusion of the project. All appropriate boxes should be checked with the necessary comments added and the form signed. The completed evaluation will be sent to:

Walter Lane
Quality Management Engineer
Indiana Department of Transportation
100 N. Senate Avenue, Room N642
Indianapolis, IN 46204-2216

The Department agrees that the information provided on this form is not a part of the contract document and is for the Department's information only, and the Department or its agents will not use any of the statements, answers, or any other information on this form against the Contractor: (1) when reviewing or considering any claim for additional compensation, (2) during litigation (specifically, it is not an admission or an admission against interest), (3) at any administrative hearing, or (4) for any other purpose whatsoever.

Please submit a separate evaluation form, if there was a difference in the quality of the roadway plans and the bridge plans.

Evaluation pertains to: ☐ Roadway Plans ☐ Bridge Plans ☐ Both ☒ Traffic Plans

GENERAL

1. Were the plans clear with sufficient detail? If no, what details were lacking or omitted?

☒ Yes ☐ No

FOR OFFICE USE ONLY	
DISTRIBUTION: Check Appropriate Boxes	
<input type="checkbox"/>	COMMISSIONER, INDOT
<input type="checkbox"/>	CHIEF ENGINEER, INDOT
<input type="checkbox"/>	DEPUTY CHIEF ENGINEER, INDOT
<input type="checkbox"/>	CHIEF, DESIGN, INDOT
<input type="checkbox"/>	CONSULTANT
<input type="checkbox"/>	COUNTY COMMISSIONER / MAYOR
<input type="checkbox"/>	COUNTY/CITY/TOWN ENGINEER
<input type="checkbox"/>	OTHER

INDOT Construction Evaluation of Plans and Contract Documents

Project Engineer's/Supervisor's Rating

District _____
Contract No. _____
Des. No. _____
Route _____
County/City/Town _____
Designer/Design Consultant _____

GENERAL (Continued)

- ☒
- Yes
- ☐
- No

1. NAME
 2. DATE
 3. TIME
 4. LOCATION
 5. REASON
 6. REMARKS
 7. SIGNATURE
 8. DATE
 9. TIME
 10. LOCATION
 11. REASON
 12. REMARKS
 13. SIGNATURE
 14. DATE
 15. TIME
 16. LOCATION
 17. REASON
 18. REMARKS
 19. SIGNATURE
 20. DATE
 21. TIME
 22. LOCATION
 23. REASON
 24. REMARKS
 25. SIGNATURE
 26. DATE
 27. TIME
 28. LOCATION
 29. REASON
 30. REMARKS
 31. SIGNATURE
 32. DATE
 33. TIME
 34. LOCATION
 35. REASON
 36. REMARKS
 37. SIGNATURE
 38. DATE
 39. TIME
 40. LOCATION
 41. REASON
 42. REMARKS
 43. SIGNATURE
 44. DATE
 45. TIME
 46. LOCATION
 47. REASON
 48. REMARKS
 49. SIGNATURE
 50. DATE
 51. TIME
 52. LOCATION
 53. REASON
 54. REMARKS
 55. SIGNATURE
 56. DATE
 57. TIME
 58. LOCATION
 59. REASON
 60. REMARKS
 61. SIGNATURE
 62. DATE
 63. TIME
 64. LOCATION
 65. REASON
 66. REMARKS
 67. SIGNATURE
 68. DATE
 69. TIME
 70. LOCATION
 71. REASON
 72. REMARKS
 73. SIGNATURE
 74. DATE
 75. TIME
 76. LOCATION
 77. REASON
 78. REMARKS
 79. SIGNATURE
 80. DATE
 81. TIME
 82. LOCATION
 83. REASON
 84. REMARKS
 85. SIGNATURE
 86. DATE
 87. TIME
 88. LOCATION
 89. REASON
 90. REMARKS
 91. SIGNATURE
 92. DATE
 93. TIME
 94. LOCATION
 95. REASON
 96. REMARKS
 97. SIGNATURE
 98. DATE
 99. TIME
 100. LOCATION
 101. REASON
 102. REMARKS
 103. SIGNATURE
 104. DATE
 105. TIME
 106. LOCATION
 107. REASON
 108. REMARKS
 109. SIGNATURE
 110. DATE
 111. TIME
 112. LOCATION
 113. REASON
 114. REMARKS
 115. SIGNATURE
 116. DATE
 117. TIME
 118. LOCATION
 119. REASON
 120. REMARKS
 121. SIGNATURE
 122. DATE
 123. TIME
 124. LOCATION
 125. REASON
 126. REMARKS
 127. SIGNATURE
 128. DATE
 129. TIME
 130. LOCATION
 131. REASON
 132. REMARKS
 133. SIGNATURE
 134. DATE
 135. TIME
 136. LOCATION
 137. REASON
 138. REMARKS
 139. SIGNATURE
 140. DATE
 141. TIME
 142. LOCATION
 143. REASON
 144. REMARKS
 145. SIGNATURE
 146. DATE
 147. TIME
 148. LOCATION
 149. REASON
 150. REMARKS
 151. SIGNATURE
 152. DATE
 153. TIME
 154. LOCATION
 155. REASON
 156. REMARKS
 157. SIGNATURE
 158. DATE
 159. TIME
 160. LOCATION
 161. REASON
 162. REMARKS
 163. SIGNATURE
 164. DATE
 165. TIME
 166. LOCATION
 167. REASON
 168. REMARKS
 169. SIGNATURE
 170. DATE
 171. TIME
 172. LOCATION
 173. REASON
 174. REMARKS
 175. SIGNATURE
 176. DATE
 177. TIME
 178. LOCATION
 179. REASON
 180. REMARKS
 181. SIGNATURE
 182. DATE
 183. TIME
 184. LOCATION
 185. REASON
 186. REMARKS
 187. SIGNATURE
 188. DATE
 189. TIME
 190. LOCATION
 191. REASON
 192. REMARKS
 193. SIGNATURE
 194. DATE
 195. TIME
 196. LOCATION
 197. REASON
 198. REMARKS
 199. SIGNATURE
 200. DATE
 201. TIME
 202. LOCATION
 203. REASON
 204. REMARKS
 205. SIGNATURE
 206. DATE
 207. TIME
 208. LOCATION
 209. REASON
 210. REMARKS
 211. SIGNATURE
 212. DATE
 213. TIME
 214. LOCATION
 215. REASON
 216. REMARKS
 217. SIGNATURE
 218. DATE
 219. TIME
 220. LOCATION
 221. REASON
 222. REMARKS
 223. SIGNATURE
 224. DATE
 225. TIME
 226. LOCATION
 227. REASON
 228. REMARKS
 229. SIGNATURE
 230. DATE
 231. TIME
 232. LOCATION
 233. REASON
 234. REMARKS
 235. SIGNATURE
 236. DATE
 237. TIME
 238. LOCATION
 239. REASON
 240. REMARKS
 241. SIGNATURE
 242. DATE
 243. TIME
 244. LOCATION
 245. REASON
 246. REMARKS
 247. SIGNATURE
 248. DATE
 249. TIME
 250. LOCATION
 251. REASON
 252. REMARKS

- ☒ Yes ☐ No

[illegible]

- ☐ Yes ☒ No

☒ No. Many of the existing floral exposures damaged and needed repair. The landscaping and ground work outside was adequate.

An undisturbed area by the traps does not account for the near certainty of failed traps in these locations. We do have been helped.

[illegible]

INDOT Construction Evaluation Report

GENERAL (Continued)

5. Did the pay items used match the work to be performed? If no, which pay items did not?
☒ Yes ☐ No

6. If the contract had working days rather than a completion date, was the number of days ...
☐ too few ☐ too many ☐ about right ☒ N/A

UTILITIES/RAILROADS

7. Were the utilities accurately shown on the plans? If no, which utilities were not properly shown and what additional information should have been provided?
☐ Yes ☒ No ☐ N/A

SOME FOUNDATION LOCATIONS HAD TO BE SLIGHTLY
ADJUSTED DUE TO UTILITY CONFLICTS, NOTICED DURING
AND CORRECTION

8. Was the project free of unknown utilities? If no, what utilities?
☐ Yes ☒ No

THE UTILITIES WERE KNOWN, BUT NOT
THAT FREQUENTLY CONSIDERED WITH THE FOUNDATION
LOCATIONS.

INDOT Construction Evaluation Report

The Construction Evaluation Form contains 23 questions related to general contract items, construction plans, utilities/railroads, right-of-way and so on. The Report organizes the 23 questions into groups. The groups are:

- **Quantities and Pay Items**
- Utilities and Railroad
- Soils and Foundations
- Structures
- **Plans, Specifications, Special Provisions**
- R/W and Maintenance of Traffic
- Permits and Contract Work Days
- **Overall Project Rating**

INDOT Construction Evaluation Report

QUANTITIES/ PAY ITEMS

Question #4: Were the quantities reliable?

	YES	NO	Total Responses	N/A	Not Answered
Reviews	375	278	653	11	12
% Yes/No	57%	43%			

Question #5: Did the pay items used match the work to be performed?

	YES	NO	Total Responses	N/A	Not Answered
Reviews	535	118	653	16	7
% Yes/No	82%	18%			

INDOT Construction Evaluation Report

SUMMARY OF CONSTRUCTABILITY SCREENING MAGNITUDE OF CHANGES

Plans- Earthwork Distribution-

23 Major Changes
39 Moderate Changes
97 Minor Changes
422 None

Summary: 62 Of 581 **(11 %)** Rated Major and Moderate Changes

Quantities -

56 Major Changes
129 Moderate Changes
279 Minor Changes
132 None

Summary: 185 of 596 **(31%)** Rated Major and Moderate Changes

Pay Items -

39 Major Changes
94 Moderate Changes
276 Minor Changes
181 None

Summary 133 of 590 **(23%)** Rated Major and Moderate Changes

INDOT Construction Evaluation Report

Quantities/ Pay Items Summary

QUANTITIES

- The most notable figure from this study of Construction Evaluations is that on average, **43% of the Construction Project Supervisors do not feel that the calculated quantities are reliable.**
- 45% of the supervisors rated the accuracy of the quantity calculations as fair or poor.**
- Of the actual change orders due to quantity errors or omissions, 31% were rated as major or moderate changes. It appears that when there are change orders due to quantity miscalculations, the required change orders for over 25% of the projects are significant.

PAY ITEMS

- In addition, on average, **18% of the Supervisors feel that the pay items in the Itemized Proposals do not match the work to be performed.**
- 30% rate the accuracy of bid items as fair to poor.**
- Of the actual change orders due to pay item revisions or omissions, 23% were rated as major or moderate changes. When change orders due to pay items are required, almost 20% of the time, the changes are considered significant.

INDOT Construction Evaluation Report

EARTHWORK DISTRIBUTION

•**11% of the Project Supervisors rated change orders due to earthwork distribution as major or moderate.** Earthwork distribution calculations do not appear to be a significant problem as compared to other incorrect pay items and quantities.

Conclusions

Based on the results of this study, it appears that overall, designers are not consistently calculating quantities correctly nor are they using the correct pay items on the Itemized Proposals. On the majority of the projects with incorrect quantities, the calculations for road items including asphalt pavement and compacted aggregate base for the shoulder wedging are some of the most common items requiring change orders. Typical errors also include pay items called out on the plans and in tables not matching quantity calculations nor the itemized proposal. In addition, on bridge projects there were several incidences where the concrete and re-bar quantities were tabulated for one element (i.e. one pier), but the quantities were not multiplied by the number of similar elements (i.e. other piers that were similar, but not detailed).

INDOT Construction Evaluation Report

PLANS/ SPECIAL PROVISIONS / SPECIFICATIONS

Question #1: Were the plans clear with sufficient detail?

	YES	NO	Total Responses	N/A	Not Answered
Reviews	482	175	657		14 5
% Yes/No	73%	27%			

Question #2: Were the special provisions clear and in sufficient detail?

	YES	NO	Total Responses	N/A	Not Answered
Reviews	603	63	666	6	4
% Yes/No	90%	10%			

Question #3: Were the Standard Specifications and the Standard Drawings clear?

	YES	NO	Total Responses	N/A	Not Answered
Reviews	607	36	643	12	20
% Yes/No	94%	6%			

INDOT Construction Evaluation Report

SUMMARY OF CONTRUCTABILITY SCREENING MAGNITUDE OF CHANGES

Plans – Alignments –

13 Major Changes
39 Moderate Changes
75 Minor Changes
456 None

Summary: 52 of 583 **(9%)** Rated Major and Moderate Changes

Plans – Drainage Plans-

25 Major Changes
52 Moderate Changes
108 Minor Changes
398 None

Summary: 77 of 583 **(13%)** Rated Major and Moderate Changes

Plans – Material Specifications-

11 Major Changes
34 Moderate Changes
84 Minor Changes
448 None

Summary: 45 of 577 **(8%)** Rated Major and Moderate Changes

Specifications –

14 Major Changes
33 Moderate Changes
86 Minor Changes
446 None

Summary: 47 of 579 **(8%)** Rated Major and Moderate Changes

INDOT Construction Evaluation Report

Plans, Special Provisions, Specifications Summary

On over 27% of the projects, the supervisors felt that the plans were not clear and did not have sufficient detail.

Of the actual change orders that were required due to plans, provisions and specifications, approximately 7% to 13% were rated as major or moderate changes.

Conclusions

Based on the results of our study, it appears that overall the project supervisors are not having difficulties dealing with the special provisions or the standard drawings. 22% though, rate the plans as not being clear nor having sufficient detail. Apparently, in general, the construction plans are lacking enough details for the projects to be constructed.

INDOT Construction Evaluation Report

OVERALL SUMMARY AND PROJECT RATING

Question #23A: Were the construction drawings and specifications complete?

	Reviews	%
Better than Expected	32	5%
Met Expectations	485	72%
Needs to Improve	80	12%
Serious Problem	9	1%
No Opinion	20	3%
Not Answered	50	7%

Question #23B: Were the construction drawings and specifications accurate?

	Reviews	%
Better than Expected	30	4%
Met Expectations	465	69%
Needs to Improve	97	14%
Serious Problem	14	2%
No Opinion	19	3%
Not Answered	51	8%

INDOT Construction Evaluation Report

Question #23C: Were there a large number of contractor questions?

	<u>Reviews</u>	<u>%</u>
Better than Expected	32	5%
Met Expectations	483	71%
Needs to Improve	70	10%
Serious Problem	8	1%
No Opinion	33	5%
Not Answered	50	8%

Question #23D: Did the construction documents impact contractor's ability to meet schedule?

	<u>Reviews</u>	<u>%</u>
Better than Expected	30	4%
Met Expectations	488	72%
Needs to Improve	56	8%
Serious Problem	15	2%
No Opinion	34	5%
Not Answered	53	9%

Road Design Breakout Session (Traffic Section)

- Traffic Squad (Review and Design)
- Traffic Design Memos
- New Standards for Sign Trusses

(Alfredo Hanza)

Road Design Breakout Session (Traffic Section)

- The Traffic Squad, part of Production Division. In our squad we are 5 engineers and our work is to design and review traffic projects. These can be specific Traffic projects or Traffic items part of large road jobs. Including lighting, signing and signals our primary review is on all traffic items of the IPOC jobs. We interact with the managers of the IPOC jobs and the consultant designers in the review of these jobs. We conduct our review on the computer and communicate with the designer by phone or email and hold meetings when necessary.
- At the beginning phase of these jobs we get with the designer on the existing scoping to define more specifically the objective of the work. At 30% of the road design we should review all existing signing and the layout of proposed messages of the signing and some of the lighting alternatives. At 60% of the design we should review all new signing cross sections and design structures. At 90% of the design we should review final traffic design. Of course we are always open to inquiries and technical advice at any time the designer feels necessary.
- All non IPOC Traffic jobs or Traffic items included on road jobs that are submitted to Coordinator 7 (which is our review squad in Production) are sent to us for review. Depending on our work load we will review or send back to the Coordinator for Consultant review.
- Our Traffic Squad does all in-house Traffic design for all road jobs assigned in-house. Also, at the District's request, we can assist with traffic design jobs when they feel assistance is needed.

Road Design Breakout Session

(Traffic Section)

- I would like to emphasize a couple of points that designers should be aware of. First, we are requiring that any traffic signal design shall have counting capabilities for vehicles in each traffic lane approaching a signalized intersection and identify the counting loops in the loop tagging table. There is a memorandum dated January 18, 2007 that explains in detail how this is to be done.
- Second, designers should be aware that our existing Signing Box Trusses standard sheet is not to be used. They need to be updated to the AASHTO 2001, 4th Edition with interims to 2007 that include the Fatigue Factor. A Design Memorandum was sent last week from our Design Resources Engineer concerning this matter.

Road Design Breakout Session (Finish)

- Questions & Answers